

Section 1 - Project Overview

PROJECT DEMO - TENDER QUESTION AND ANSWER (TQA)

Name of Tenderer: ACME DESIGN AND CONSTRUCTION PTE. LTD.

Date of issue: 8 Nov 2019

This document consolidates all Tender Clarifications raised by the Tenderer and the corresponding answers issued by the Authority during the tender period.

Section 1 defines key terminology used throughout the contract. TSA refers to Temporary Staging Area, a designated zone on the construction site where materials, equipment, and contractor facilities may be located during the works. The total TSA allocated to the DEMO project consists of two parcels: a primary TSA of 0.86 hectares and a secondary TSA of 0.25 hectares, providing a total of 1.11 hectares of temporary staging area.

Refer to Drawing No. T/PRJ/CWD/WS/2101A for the spatial layout of both TSA parcels and Clause 7 of the Particular Specification for the conditions of use.

Section 7 - Civil and Trackwork Interface

Question No.: ACME/TRACKWORK/16

Date of issue: 8 Nov 2019

Subject: Civil and Trackwork Interface

Question: Refer to Drawing 201436-BEN-T-1180 Rev A interface details between viaduct beams at pier, the screed to waterproofing is stated as to be provided by Trackwork Contractor. This deviates from the Authority's Drawing No. T/PRJ/CWD/CV/7021/A. Please confirm that you will follow the arrangement shown on Authority's Drawing.

Answer (Revision 0):

We confirm. The screed to waterproofing at the pier shall be provided by the Trackwork Contractor in accordance with Authority Drawing No. T/PRJ/CWD/CV/7021/A and Clause 7.3 of the Particular Specification. The Tenderer's interface drawing shall be revised to align with the Authority's drawing prior to contract execution.

Section 7 - Tender Clarification Procedure

Question No.: ACME/PROC/04

Subject: Tender Clarification Submission Procedure

Question: Please clarify the procedure for submitting tender clarifications and the expected turnaround time for responses.

Answer (Revision 0):

Tender Clarifications shall be submitted in writing to the Authority's representative via email, with a copy to the designated project mailbox. Each clarification shall reference the relevant Section, Clause, and Drawing No. where applicable. The Authority shall endeavour to respond within ten (10) working days of receipt. Responses may be issued as Revision 0 (initial) or subsequent revisions (Rev A, Rev B, etc.) where additional clarification is needed.

Section 7 - Civil and Trackwork Interface (cont.)

Question No.: ACME/TRACKWORK/16 (Rev A)

Revised Answer (Rev A):

Further to Revision 0, the Trackwork Contractor's scope is expanded to include not only the screed to waterproofing at viaduct beam piers but also the corresponding inspection and snagging works prior to handover. Refer to Drawing No. T/PRJ/CWD/CV/7021/A for the updated interface details. Clause 7.3 of the Particular Specification governs the responsibility split. This Rev A supersedes Revision 0 in its entirety.

Section 7 references: Clause 7.1 (Scope), Clause 7.3 (Civil/Trackwork interface responsibility), Clause 7.5 (Acceptance criteria), and Drawing T/PRJ/CWD/WS/2101A (site layout).